

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-093-20340-00-00
 Spot: SWSE Sec/Twnshp/Rge: 13-21S-35W
663 feet from S Section Line, 1947 feet from E Section Line
 Lease Name: MILLER Well #: C1
 County: KEARNY Total Vertical Depth: 2710 feet

Operator License No.: 32198
 Op Name: PETROSANTANDER (USA) INC.
 Address: 6363 WOODWAY DR STE350
HOUSTON, TX 77057

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2100		WITH 2 SX CMT
CIBP		2520		WITH 2 SX CMT
PROD	4.5	2706	0	WITH 400 SX CMT
SURF	8.625	618		WITH 250 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/21/2017 9:00 AM
 Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
 Proposal Revd. from: PETE KUNEYL Company: PETROSANTANDER Phone: (620) 275-2388

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
 Date/Time Plugging Completed: 07/21/2017 12:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2520' WITH 2 SX CMT. TEST CASING TO 1000#. HOLDING. CIBP AT 2100' WITH 2 SX CMT. PERFORATE 4 HOLES AT 1000'. INJECTION RATE 2 BPM AT 400#. PUMP 55 SX CMT, 50# HULLS THEN 25 SX CMT VIA 4 1/2" CASING. DISPLACE TO 650' AT 550# LEAVING 55 SX CMT OUTSIDE THE 4 1/2" CASING & 25 SX CMT INSIDE THE 4 1/2" CASING. PERFORATE 4 HOLES AT 630'. CIRCULATE CMT TO SURFACE THROUGH PERFS AT 630' USING 220 SX CMT LEAVING THE 4 1/2" CASING & 4 1/2" X 8 5/8" ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
2632	2649		
2601	2608		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed *Ken Jehlik*
 (TECHNICIAN)

RECEIVED
 JUL 27 2017
 KCC DODGE CITY

INVOICED
 AUG 29 2017