

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-135-25949-00-00  
Spot: NWSWSENE Sec/Twship/Rge: 17-16S-24W  
3160 feet from S Section Line, 1255 feet from E Section Line  
Lease Name: LAFON TRUST B Well #: 1  
County: NESS Total Vertical Depth: 4598 feet

Operator License No.: 5123  
Op Name: PICKRELL DRILLING COMPANY, INC.  
Address: 100 S MAIN STE 505  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4450		WITH 2 SX CMT
PC	4.5	1896	1920	NOT CEMENTED
PROD	4.5	4598		WITH 145 SX CMT
SURF	8.625	207		WITH 150 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/07/2017 8:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JASON RATLIFF Company: PICKRELL DRILLING Phone: (785) 798-5027

Proposed Plugging Method: SET CIBP 50' ABOVE PERFS. PLUG AT 1890' WITH 50 SX CMT. PLUG AT 1050' WITH 80 SX CMT. PLUG AT 550' WITH 40 SX CMT. PLUG AT 240' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/07/2017 11:30 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4450' WITH 2 SX CMT. 1ST PLUG AT 1900' WITH 50 SX CMT & 100# HULLS. 2ND PLUG AT 1060' WITH 80 SX CMT & 300# HULLS. 3RD PLUG AT 570' WITH 40 SX CMT. 4TH PLUG AT 240' WITH 50 SX CMT. 5TH PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4544	4548		
4496	4500		
4482	4484		

INVOICED  
AUG 29 2017

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed Michael Maier  
MA (TECHNICIAN)

RECEIVED  
JUL 11 2017  
KCC DODGE CITY