

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-185-01020-00-01  
Spot: SENWSW Sec/Twnslp/Rge: 2-24S-15W  
1686 feet from S Section Line, 4287 feet from E Section Line  
Lease Name: DORAN Well #: 1  
County: STAFFORD Total Vertical Depth: 4180 feet

Operator License No.: 5086  
Op Name: PINTAIL PETROLEUM, LTD.  
Address: 225 N MARKET STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3940		WITH 2 SX CMT
PROD	5.5	4173	0	WITH 125 SX CMT
SURF	10.75	255		

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/26/2017 9:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Revd. from: STEVE JONES Company: PINTAIL PETROLEUM Phone: (620) 546-3856

Proposed Plugging Method: CIBP @ 3970' & 2 SX CMT. PERFORATE AT 1000' WITH 25 SX CMT, 100# HULLS, 25 SX CMT. PERFORATE AT 380' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/28/2017 12:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

SET CIBP @ 3940' & TOP WITH 2 SX CMT. PERFORATE AT 1000' & 380' WITH 2 SHOTS EACH. TRIP IN HOLE WITH 2 3/8" TBG TO 1015' & BREAK CIRCULATION WITH FRESH WATER. GOOD RETURNS BOTH INSIDE & ON BACKSIDE OF CASING. PUMP 15 SX GEL FOLLOWED BY 25 SX CMT WITH 100# HULLS IN LAST 25 SX OF CMT. PULL TBG OUT OF HOLE TO 409' & BREAK CIRCULATION WITH FRESH WATER WITH RETURNS IN & OUTSIDE 5 1/2" CASING. PUMP 190 SX CMT WITHOUT GETTING CMT TO SURFACE. WAIT ON CMT 3 HOURS. PUMP 75 SX CMT WITH 4% CC AT 380'. SMALL AMOUNT OF WATER RETURNED TO SURFACE ON BACKSIDE OF 5 1/2" CASING. PUL TBG OUT OF HOLE & SHUT DOWN FOR DAY. 6/27/17: PICK UP 2 3/8" TBG & TAGGED CMT AT 130'. 10 SX CMT USED TO FILL 5 1/2" CASING & 10 SX CMT IN THE ANNULUS.

Perfs:

Top	Bot	Thru	Comments
4020	4082		


INVOICED

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY SERVICES.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED  
JUL 13 2017  
KCC DODGE CITY

