

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-24569-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 11-13S-18W
4950 feet from S Section Line, 990 feet from E Section Line
Lease Name: DREILING Well #: 1-11
County: ELLIS Total Vertical Depth: 3749 feet

Operator License No.: 5386
Op Name: PRODUCTION DRILLING, INC.
Address: 1023 RESERVATION RD
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3749		125 SX
SURF	8.625	206		140 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/05/2017 9:00 AM
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE
Proposal Rcvd. from: NIK GABEL Company: ROME CORPORATION DBA WEST Phone: (785) 623-0349

Proposed Plugging Method: Ordered 250 sx 60/40 pozmix 4% gel cement, 7 bags gel (700 #) and 500 # hulls.
Multi stage collar at 1426' w/125 sx cement.
Arb: 3678' - 3701'.
PBSD: 3728'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/05/2017 2:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Western Well Service ran in hole with tubing to 3589'. Quality rigged to tubing and pumped 7 sx gel followed by 50 sx cement w/200 # hulls mixed in. Pulled tubing to 1859' and pumped 110 sx cement w/300 # hulls mixed in to circulate cement to surface. Pulled tubing. Rigged to 4 1/2" casing and pumped 15 sx cement to pressure with 200 psi. Shut in pressure 200 psi. Rigged to 8 5/8" surface casing and pumped 20 sx cement to pressure with 200 psi. Shut in pressure 200 psi.

GPS: 38.94256 -099.28315

Perfs:

Top	Bot	Thru	Comments
3678	3701		

Remarks: QUALITY CEMENTING CO TICKET # 257

Plugged through: TBG

District: 04

Signed

KCC WICHITA

(TECHNICIAN)

CM

JUL 10 2017

JUL 20 2017

RECEIVED

Form CP-2/3

INVOICED
AUG 29 2017