

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-22409-00-00
Spot: NWSE Sec/Twnshp/Rge: 12-20S-10W
1995 feet from S Section Line, 1986 feet from E Section Line
Lease Name: SCHURBERT Well #: 4
County: RICE Total Vertical Depth: 3323 feet

Operator License No.: 3911

String Size Depth (ft) Pulled (ft) Comments

Op Name: RAMA OPERATING CO., INC.

CIBP 5.5 3000

Address: 101 S MAIN ST
STAFFORD, KS 67578

PROD 5.5 3322 165 SX

SURF 8.625 238 165 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 07/13/2017 9:00 AM

Plug Co. License No.: 34069

Plug Co. Name: BASIC ENERGY SERVICES, LP

Proposal Rcvd. from: RANDY GINEST

Company: RAMA OPERATING

Phone: (620) 546-3388

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JONATHAN HILL

Witness Type: PARTIAL

Date/Time Plugging Completed: 07/13/2017 12:00 PM

KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, ATTEMPT MIT OF CASING - PRESSURE WOULDN'T HOLD. CIBP SET AT 3000' AND CAPPED WITH 2 SX'S CEMENT. CUT CASING OFF AT 1400' AND PULL TO 1300' AND PUMP 35 SX'S COMMON WITH 2% CC. PULL CASING UP TO 900' AND WAIT 1 HOUR. TAG CEMENT AT 1275'. PUMPED 35 SX'S COMMON WITH 2% CC AT 900'. PULLED CASING TO 290' AND CIRCULATED CEMENT TO SURFACE. PULLED CASING OUT AND TOPPED OFF. USED APPROX. 180 SX'S.

Perfs:

Top	Bot	Thru	Comments
3032	3074	CSG	

Remarks: DENIED TA WELL. BASIC SERVICES #15306

Plugged through: CSG

INVOICED
AUG 29 2017

District: 02

Signed Virgil Clothier
(TECHNICIAN)

134