

TO:  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING  
 266 N. Main St., Ste. 220  
 Wichita, KS 67202-1513

API Well Number: 15-033-21754-01-00  
 Spot: SESWSESE Sec/Twnshp/Rge: 2-34S-20W  
313 feet from S Section Line, 804 feet from E Section Line  
 Lease Name: HANK 3420 Well #: 1-2H  
 County: COMANCHE Total Vertical Depth: 5179 feet

Operator License No.: 34192  
 Op Name: SANDRIDGE EXPLORATION AND PRO  
 Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5175		WITH 100 SX CMT
COND	20	120		WITH 12 SX CMT
	11 7	5655	1117	WITH 340 SX CMT
	LI 4.5	7542	0	
SURF	9.625	726		WITH 755 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/28/2017 1:00 PM  
 Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
 Proposal Revd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 5175' WITH 100 SX CMT. PLUG AT 780' WITH 60 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 64' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: PARTIAL  
 Date/Time Plugging Completed: 06/28/2017 4:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

TOP OF 4 1/2" LINER AT 5403'. SET CIBP @ 5175'. CIRCULATE HOLE WITH 190 BBL MUD THEN SPOTTED 100 SX CMT ON TOP OF CIBP. 1ST PLUG AT 780' WITH 60 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 64' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
7351	7419		
7177	7284		
7005	7115		
6827	6928		
6669	6772		
6457	6624		
6277	6375		
6086	6222		
5600	5912		

INVOICED  
 AUG 29 2017

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR SENT\*\* USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed [Signature]  
 (TECHNICIAN)

RECEIVED  
 JUL 11 2017  
 KCC DODGE CITY