

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-097-21091-00-00
 Spot: NWSEWSW Sec/Twnshp/Rge: 11-29S-18W
652 feet from S Section Line, 4584 feet from E Section Line
 Lease Name: SLIEF Well #: 1
 County: KIOWA Total Vertical Depth: 4960 feet

Operator License No.: 3959
 Op Name: SIROKY OIL MANAGEMENT
 Address: PO BOX 464
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4180		WITH 2 SX CMT
DVT		3620		
PROD	4.5	4984	0	WITH 100 SX CMT
SURF	8.625	417		WITH 350 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 07/27/2017 2:00 PM
 Plug Co. License No.: 34484 Plug Co. Name: FOSSIL DRILLING, INC.
 Proposal Revd. from: BRIAN SIROKY Company: SIROKY OIL MANAGEMENT Phone: (620) 770-0969

Proposed Plugging Method: CIBP @ 4820' WITH 2 SX CMT. PLUG AT 1150' WITH 25 SX CMT. IF RECOVERING CASING PLUG AT 450' WITH 50 SX CMT. PLUG AT 0-40' WITH 20 SX CMT. IF NO CASING RECOVERY PERFORATE AT 450' & CIRCULATE INSIDE.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: PARTIAL
 Date/Time Plugging Completed: 07/27/2017 3:45 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

CIBP @ 4180' WITH 2 SX CMT. RUN BOND LOG 1200' TO 0'. CMT 720' TO 600' ON BACKSIDE. PERFORATE AT 1190' & PUMP 25 SX CMT & 25 SX CMT WITH 100# HULLS. PULL TBG TO 450' PUMP 150 SX CMT TO GET CMT UP 4 1/2" X 8 5/8" ANNULUS. FILL UP 4 1/2" CASING WITH 10 SX CMT. PULL TBG. TOP OFF 5 SX IN 4 1/2" & 5 SX IN ANNULUS. 220 SX CMT TOTAL FOR JOB.

Perfs:

Top	Bot	Thru	Comments
4904	4920		
4894	4903		
4886	4888		
4874	4882		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY BASIC SERVICES.

Plugged through: TBG

INVOICED
 AUG 29 2017

District: 01

Signed _____

[Signature]
 (TECHNICIAN)

RECEIVED
 JUL 31 2017
 KCC DODGE CITY

[Signature]