

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-097-21780-00-00
Spot: NENWENW Sec/Twnshp/Rge: 1-27S-20W
5099 feet from S Section Line, 3488 feet from E Section Line
Lease Name: MILLER TRUST Well #: 'B' 1-1
County: KIOWA Total Vertical Depth: 4972 feet

Operator License No.: 33036
Op Name: STRATA EXPLORATION, INC.
Address: PO BOX 401
FAIRFIELD, IL 62837

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4170		WITH 2 SX CMT
PC	5.5	2720		WITH 125 SX CMT
PROD	5.5	4414	0	WITH 125 SX CMT
SURF	8.625	620		WITH 365 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 07/18/2017 9:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: SHANE PELTON Company: STRATA EXPLORATION Phone: (719) 340-8987

Proposed Plugging Method: CIBP @ 4170' WITH 2 SX CMT. CMT FROM 1330' TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: LARRY HARRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/18/2017 10:50 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

SET CIBP @ 4170' WITH 2 SX CMT. RAN TBG TO 1345' & CIRCULATED CMT TO SURFACE WITH 150 SX CMT. PULLED TBG & TOPPED OFF WITH 5 SX CMT. TIED ONTO BACKSIDE & PRESSURED TO 200# WITH 15 SX CMT.

Top	Bot	Thru	Comments
4222	4231		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY SERVICES.

Plugged through: TBG

INVOICED
AUG 29 2017

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
JUL 25 2017
KCC DODGE CITY