

TO:

API Well Number: 15-073-19840-00-00

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

Spot: SEWSE

Sec/Twnshp/Rge: 12-22S-10E

1650 feet from S Section Line, 1650 feet from E Section Line

Lease Name: D & S (DEMALORIE)

Well #: W 33 (68)

County: GREENWOOD

Total Vertical Depth: 2141 feet

Operator License No.: 5394

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6.63	2050		950 SX
SURF	0	0		0 SX

Op Name: ABDERHALDEN, R. R.

Address: 100 S. MAIN, STE 510
WICHITA, KS 67202

Well Type: EOR

UIC Docket No: E03423.36

Date/Time to Plug: 08/01/2017 12:00 PM

Plug Co. License No.: 5656

Plug Co. Name: R.R.A., INC.

Proposal Rcvd. from: DWAIN G STOUT

Company:

Phone: (316) 640-9072

Proposed Plugging Method: Run tubing to TD and set a 50 ft cement plug. Pump gel to 700 ft. and set a 50 ft. cement plug. Pump gel to 250 ft. and cement to surface.

Plugging Proposal Received By: MICHAEL HEFFERN

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 08/01/2017 4:00 PM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

ran tubing to 1997', pumped 20 sxs cement, pulled tubing to 730', pumped 20 sxs cement, pulled tubing to 250', pumped 80 sxs cement, gel spacers between cement plugs

RECEIVED
KCC DIST # 3
AUG 14 2017
CHANUTE, KS

MH

INVOICED
AUG 6 1 2017

Remarks:

Plugged through: TBG

District: 03

Signed

Mike Heffern
(TECHNICIAN)

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



15-073-19840 0000

Cement or Acid Field Report
 Ticket No. **3451**
 Foreman Rick Ledford
 Camp Eureka KS

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
8-1-17	104L	D+S W-33				GW	KS
Customer <u>R.R.A Inc.</u>			Safety Meeting <u>RL</u>	Unit # <u>102</u>	Driver <u>Rick L.</u>	Unit #	Driver
Mailing Address <u>100 S. Main St. Ste 510</u>			<u>SM</u>	<u>112</u>	<u>Steve M.</u>		
City <u>Wichita</u> State <u>KS</u> Zip Code <u>67202</u>			<u>CM</u>		<u>Gary D.</u>		

Job Type P.T.A Hole Depth _____ Slurry Vol. _____ Tubing 2 3/4"
 Casing Depth _____ Hole Size _____ Slurry Wt. 17.8" Drill Pipe _____
 Casing Size & Wt. 6 5/8" Cement Left in Casing _____ Water Gal/SK 70 Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety meeting - Rig up to 2 3/4" tubing. Plugging notes as follows
20 SKS @ 1997'
20 SKS @ 730'
20 SKS @ 250' to surface

Note: Get spaces between plugs.

"Thank You"

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C105	1	Pump Charge	750.00	750.00
C107	20	Mileage	3.95	79.00
C203	120 SKS	60/40 Perm mix cement	12.75	1530.00
C206	410"	4% gel	.20	82.00
C206	400"	gel-spacer	.20	80.00
C102A	5.16	tax mileage bulk tax	m/c	345.00
			7.5%	
			Subtotal	2866.00
			Sales Tax	

Authorization by Dwain Stout Title Co. Rep. Total _____

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.