

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-21166-00-00
Spot: SENWNWNW Sec/Twnshp/Rge: 13-15S-29W
4694 feet from S Section Line, 4948 feet from E Section Line
Lease Name: FULLMER Well #: 2-H
County: GOVE Total Vertical Depth: 4290 feet

Operator License No.: 32457
Op Name: ABERCROMBIE ENERGY, LLC
Address: 10209 W. CENTRAL, STE 2
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4204		150 SX
SURF	8.625	369		200 SX

Well Type: EOR UIC Docket No: E27356.1 Date/Time to Plug: 07/12/2017 9:30 AM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Rcvd. from: TIM JULIAN Company: ABERCROMBIE ENERGY, LLC DB Phone: (620) 793-8186

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Alt II Squeeze at 2200' w/400 sx cement.
Perforations: 3897' - 3900'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/12/2017 1:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3886' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 2883' and pumped 100 sx cement w/100 # hulls. Lost circulation on clean up. Pulled tubing to 2083' and pumped 175 sx cement w/100 # hulls. Good circulation of cement. Pulled tubing. Topped off casing with 15 sx cement. Tied on to backside and squeezed with 100 sx cement. Shut in pressure 80 psi.

GPS: 38.75602 -100.50246

Perfs:

Top	Bot	Thru	Comments
3897	3900		

Remarks: QES CEMENT TICKET # 53560

Plugged through: TBG

INVOICED

AUG 01 2017

District: 04

Signed

KCC WICHITA

JUL 20 2017

RECEIVED

(TECHNICIAN)

CM

JUL 14 2017