

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-20271-00-01
Spot: W2SWSWSE Sec/Twnshp/Rge: 16-14S-28W
330 feet from S Section Line, 2330 feet from E Section Line
Lease Name: COBERLY JJ Well #: 3
County: GOVE Total Vertical Depth: 4342 feet

Operator License No.: 34888
Op Name: AMERICAN OIL LLC
Address: 1200 MAIN SUITE 410
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4341		200 SX
SURF	8.625	335		225 SX

Well Type: EOR UIC Docket No: E28047.6 Date/Time to Plug: 07/11/2017 11:00 AM
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE
Proposal Rcvd. from: JODY DUMLER Company: AMERICAN OIL LLC DBA Phone: (785) 445-8279

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Perforations at 3954' - 4018'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/11/2017 2:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perforated at 1117', 2062' and 2481'. Ran tubing to 3953' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 2974' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 1560' and pumped 110 sx cement. Cement circulated. Pulled tubing out and topped off with 20 sx cement. Tied on to backside and squeezed with 5 sx cement. Shut in pressure 300 psi.

GPS: 38.83012 -100.43645

Perfs:

Top	Bot	Thru	Comments
3954	4018		

Remarks: QUALITY CEMENT TICKET # 1586

Plugged through: TBG


INVOICED

AUG 01 2017

District: 04

KCC WICHITA

Signed



(TECHNICIAN)

CM

JUL 20 2017

RECEIVED

JUL 17 2017