

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-20870-00-01
Spot: SWSENWNW Sec/Twnshp/Rge: 27-25S-5E
3996 feet from S Section Line, 4572 feet from E Section Line
Lease Name: MILLS Well #: 2-C
County: BUTLER Total Vertical Depth: 2559 feet

Operator License No.: 33192
Op Name: CROWN ENERGY COMPANY
Address: 1117 N.W. 24TH ST.
OKLAHOMA CITY, OK 73106

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	630		
PROD	5.5	2559		0 SX
SURF	0	0		0 SX
SURF		94		

Well Type: EOR UIC Docket No: E06333.1 Date/Time to Plug: 07/17/2017 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICK HART/HAYS WILSON Company: CROWN ENERGY CO Phone: (405) 526-0111

Proposed Plugging Method: AS PER KCC REGS & RULES

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 07/18/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

POOH W/ TUBING & PACKER, 18 JOINTS OF TUBING (620') RIH W/WORK STRING @ 634', TAGGED SOLID. PERFORATED SQUEEZE HOLES 250-251'. (4 HOLES). WITH TUBING @ 614' QUALITY WELL SERVICE ESTABLISHED CIRCULATION, MIXED & PUMPED 25 SXS 60/40 POZMIX, 200# HULLS & DISPLACED IN CASING. FLUID HELD AT SURFACE. PULLED TUBING @ 260', QUALITY MIXED & PUMPED 80 SXS 60/40 POZMIX 4% GEL TO SURFACE, LAYED DOWN TUBING. SWEDGED INTO CASING & PUMPED 5 SXS 60/40 POZMIX 4% GEL. SIP AT 200#. SWEDGED INTO BACKSIDE OF PRODUCTION CASING & PUMPED 10 SXS 60/40 POZMIX. SIP 200#. CEMENT CIRCULATED. P&A COMPLETE.

Perfs:

Top	Bot	Thru	Comments
624	626	CSG	

INVOICED
AUG 24 2017

Remarks: FAILED MIT

Plugged through: TBG

District: 02

Signed

Duane Krueger
(TECHNICIAN)