

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-125-29156-00-00  
Spot: SWNWNE Sec/Twnshp/Rge: 2-34S-13E  
4313 feet from S Section Line, 2291 feet from E Section Line  
Lease Name: MANN A B Well #: KHHA 2  
County: MONTGOMERY Total Vertical Depth: 1917 feet

Operator License No.: 31696  
Op Name: CUNNINGHAM CRUDE, A GENERAL P  
Address: 3343 CR 2200  
INDEPENDENCE, KS 67301

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	1917		0 SX
SURF	7	31		0 SX

Well Type: SWD UIC Docket No: D25713.0 Date/Time to Plug: 07/06/2017 12:00 AM

Plug Co. License No.: 31696 Plug Co. Name: CUNNINGHAM CRUDE, A GENERAL PARTNERSHIP

Proposal Rcvd. from: RON CUNNINGHAM Company: Phone: (620) 289-4700

Proposed Plugging Method: Run 1" to bottom, gel hole, spot 2 sacks of cement on bottom (50' plug), pull up to 1100', spot 2 sacks of cement (50' plug), pull up to 500', spot 2 sacks of cement (50' plug), pull up to 225', cement to surface, pull tubing out of hole, top off cement, cut surface and production casing off at 4' below surface, restore location.

Plugging Proposal Received By:

WitnessType: NONE

Date/Time Plugging Completed: 07/06/2017 12:00 AM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 1819' gelled hole and spotted 2 sack plug. Pulled up to 1100' and spotted 2 sack plug. Pulled up to 500' and spotted 2 sack plug. Pulled up to 225' and circulated cement to surface. Pulled 1" and topped well off. A total of 13 sacks of cement were used to plug this well.

RECEIVED  
KCC DIST # 3  
JUL 11 2017  
CHANUTE, KS

DS


INVOICED  
AUG 24 2017

Remarks: WELL WAS PLUGGED DUE TO FAILED MIT.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)