

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-22535-00-01
Spot: NESESWNE Sec/Twnshp/Rge: 21-31S-4E
3093 feet from S Section Line, 1407 feet from E Section Line
Lease Name: HITTLE Well #: 1-A
County: COWLEY Total Vertical Depth: 3400 feet

Operator License No.: 33367
Op Name: EXPLO OIL, INC.
Address: 2000 N. CENTRAL EXPRESSWAY, STE 1
PLANO, TX 75074

String	Size	Depth (ft)	Pulled (ft)	Comments
PKR		3300		PACKER TYPE AND SETTING DEPTH: HOWCO R-4 SET @ 3300'
PROD	5.65	3400		250 SX
SURF	8.265	210		150 SX
T1	2.875	3300		

Well Type: SWD UIC Docket No: D28896.0 Date/Time to Plug: 06/28/2017 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: DICK SCHREMMER Company: GRESSEL OIL FIELD SERVICE Phone: (316) 524-1225

Proposed Plugging Method: AS PER KCC RULES & REGS/ CIBP @ 3250 W 4 SXS/PERF & CIRCULATE 260'-0'.

Plugging Proposal Received By: JEFF KLOCK WitnessType: NONE
Date/Time Plugging Completed: 06/29/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

TUBING & PACKER HUNG UP IN HOLE, SWEDGED INTO TUBING. COPELAND ACID SERVICE MIXED & PUMPED 100 SXS CLASS A COMMON, 200# HULLS & 3% CC, SIP 200#. BACKED OFF TUBING @ 1290', W/TUBING @ 1280', COPELAND ACID MIXED & PUMPED 40 SXS CLASS A COMMON 3% CC & DUMPED IN CASING. PERFORATED SQUEEZE HOLES @ 260'-261' 4 (HOLES). RIH W/TUBING @ 270', COPELAND ACID MIXED & PUMPED 110 SXS 60/40 POZMIX 2% GEL TO SURFACE. CEMENT CIRCULATED. TICKET #44910.

Perfs:

Top	Bot	Thru	Comments
3300	3350	CSG	

INVOICED
AUG 29 2017

Remarks: FAILED MIT/ 2010' 2 7/8" TUBING & PACKER LEFT IN HOLE.

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER
(TECHNICIAN)