

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-19058-00-01
Spot: NESWNESE Sec/Twnshp/Rge: 5-17S-23W
1967 feet from S Section Line, 683 feet from E Section Line
Lease Name: HARKNESS D Well #: 2
County: NESS Total Vertical Depth: 4497 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3800		
CIBP		4458		
PROD	5.5	4493	0	WITH 150 SX CMT
SURF	8.625	401		WITH 250 SX CMT

Well Type: SWD UIC Docket No: D14678.0 Date/Time to Plug: 07/12/2017 11:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: TOM MELLAND Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: RUN TBG TO BOTTOM & CIRCULATE CMT & HULLS TO SURFACE. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/12/2017 3:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

PERFS AT 3750'-3797' WERE SQUEEZED OFF WITH 100 SX CMT. THE CASING WAS PERFORATED AT 1400' & CEMENTED WITH 550 SX CMT. RUN TBG TO 1200' & PUMPED 70 SX CMT. TRUCK BROKE DOWN. PULLED TBG. WAITED 2 1/2 HOURS. RUN TBG IN TO 259' & FOUND CMT. PUMPED 35 SX CMT & CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 5 SX CMT. TIED ONTO BACKSIDE & PUMPED 35 SX CMT. PRESSURED TO 300# & HELD.

Top	Bot	Thru	Comments
4461	4462		
4416	4424		
3750	3797		
1206	1250		

Remarks: USED 60/40 POZMIX 4% GEL BY HURRICANE.

INVOICED
AUG 29 2017

Plugged through: TBG

District: 01

Signed: Michael Maier
(TECHNICIAN)

RECEIVED
JUL 18 2017
KCC DODGE CITY