

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-163-22554-00-03  
Spot: SESWSE Sec/Twnshp/Rge: 3-7S-20W  
330 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: SANDRA K GOTTSCHALK (PR Well #: 4  
County: ROOKS Total Vertical Depth: 1838 feet

Operator License No.: 5011  
Op Name: VIKING RESOURCES, INC  
Address: 400 N WOODLAWN ST, STE 18  
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3656		200 SX
SURF	8.625	329		250 SX

Well Type: SWD UIC Docket No: D28984.0 Date/Time to Plug: 06/20/2017 9:00 AM  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
Proposal Rcvd. from: SHAWN DEVLIN Company: VIKING RESOURCES, INC DBA Phone: (316) 262-2502

Proposed Plugging Method: Ordered 250 sx 60/40 pozmix 4% gel cement w/600 # hulls.  
Inj. Perforations 1440' - 1460'.  
DV Tool at 1741' w/500 sx cement.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/20/2017 10:00 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 4 1/2" casing and pumped 20 sx cement followed by 160 sx cement w/600 # hulls.  
Shut in pressure 350 psi. Visually checked 8 45/8" x 4 1/2" annulus and cement was to surface.  
GPS: 39.46733N -099.53419W

Perfs:

Top	Bot	Thru	Comments
1420	1460		

Remarks: HURRICANE SERVICES TICKET # 100755

Plugged through: CSG

INVOICED  
AUG 30 2017  
INVOICED  
AUG 29 2017

District: 04

KCC WICHITA

Signed

*Pat Bedore*

(TECHNICIAN)

CM

JUL 20 2017

RECEIVED

JUL 26 2017