

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-001-23031-00-01
Spot: SWSWNW Sec/Twnshp/Rge: 36-23S-17E
2758 feet from S Section Line, 4792 feet from E Section Line
Lease Name: NICHOLS Well #: 2
County: ALLEN Total Vertical Depth: 1200 feet

Operator License No.: 30925
Op Name: YOCHAM, DARRELL DBA YOCHAM OI
Address: 870 W VIRGINIA RD
COLONY, KS 66015

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD		1200		
SURF		20		

Well Type: EOR UIC Docket No: E24344.2 Date/Time to Plug: 08/02/2017 8:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: MIKE WIMSETT Company: W & W PRODUCTION COMPANY Phone:

Proposed Plugging Method: Run 1" pipe to TD. Circulate cement to surface.

Plugging Proposal Received By: RYAN DULING Witness Type: NONE
Date/Time Plugging Completed: 08/02/2017 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe down the inside of the 2.875" casing to 650'. Hit hard. Washed on hole for approximately 2 hours. Tried overshot to see if pipe could be retrieved. No success. Pumped and circulated cement through the 1" pipe inside the 2.875" casing from 650' to surface. Pulled 1" pipe out of the casing. Connected directly to casing and squeezed cement into the 2.875" casing. Shut in at 550 psi. A total of 20 sacks of portland cement was reported used to plug this well.

Perfs:

RECEIVED
KCC DIST # 3
AUG 08 2017
CHANUTE, KS

RD

Remarks: PLUGGED DUE TO A FAILED MIT.

Plugged through: TBG

District: 03

Signed [Signature]
(TECHNICIAN)

INVOICED
AUG 30 2017