

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-21536-00-00
Spot: SENWSW Sec/Twnshp/Rge: 22-10S-18W
1650 feet from S Section Line, 4290 feet from E Section Line
Lease Name: EILERS B Well #: 5
County: ROOKS Total Vertical Depth: 3749 feet

Operator License No.: <u>31569</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>BACH, JASON DBA BACH OIL PRODUC</u>	L1	3.5	3400		125 sx
Address: <u>PO BOX 723</u>	PROD	4.5	3749		300sx
<u>ALMA, NE 68920</u>	SURF	8.625	253		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/13/2017 1:00 PM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Rcvd. from: DALE FERLAND Company: BACH, JASON DBA BACH OIL PRO Phone: (785) 302-1435

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Production perforations: 3302' - 3590'
DV Tool at 1490' w/300 sx cement.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/13/2017 4:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3315' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 2510' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 1400' and pumped 130 sx cement w/100 # hulls to circulate cement to surface. Pulled tubing. Topped off 3 1/2" casing w/20 sx cement. Hooked to 8 5/8" x 4 1/2" annulus and pressured to 500 psi.

Perfs:

Top	Bot	Thru	Comments
3302	3590		

Remarks: GLOBAL CEMENTING TICKET # 3012
Plugged through: TBG

INVOICE
AUG 22

District: 04 Signed: Pat Bedore
KCC WICHITA (TECHNICIAN) CM

JUL 14 2017
RECEIVED