

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-137-20634-00-00  
Spot: NWNWSENE Sec/Twnshp/Rge: 26-3S-22W  
1590 feet from N Section Line, 1170 feet from E Section Line  
Lease Name: ESSLINGER RANCH INC Well #: 3-26  
County: NORTON Total Vertical Depth: 3903 feet

Operator License No.: 32819  
Op Name: BAIRD OIL COMPANY LLC  
Address: 113 W MAIN PO BOX 428  
LOGAN, KS 67646

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3902		240 SX
SURF	8.625	221		160 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/13/2017 10:00 AM  
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING  
Proposal Rcvd. from: BRYANT REESE Company: BAIRD OIL COMPANY LLC Phone: (785) 689-7456

Proposed Plugging Method: Ordered 315 sx 60/40 pozmix 4% gel cement, 12 sx gel (100 # bags) and 300 # hulls.  
Port Collar at 2073' w/155 sx cement.  
Production perforations: 3746' - 3749'

Plugging Proposal Received By: PAT BEDORE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/13/2017 11:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 5 1/2" casing and pumped 50 sx cement w/200 # hulls, then pumped 12 sx gel followed by 200 sx cement w/50 # hulls. Shut in pressure 300 psi. Hooked to 8 5/8" x 5 1/2" annulus and pumped 10 sx cement. Shut in pressure 200 psi.

GPS: 39.76583N -099.76251W

Perfs:

Top	Bot	Thru	Comments
3746	3749		

Remarks: GLOBAL OILFIELD SERVICE TICKET # 2978

Plugged through: CSG

INVOICED  
AUG 22 2017

INVOICED  
AUG 22 2017

District: 04

Signed Pat Bedore  
KCC WICHITA

(TECHNICIAN)

CM

JUL 20 2017

RECEIVED

JUN 16 2017