

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-23384-00-00
Spot: SWNENESW Sec/Twnshp/Rge: 19-7S-20W
2270 feet from S Section Line, 2160 feet from W Section Line
Lease Name: ATKISSON Well #: 1
County: ROOKS Total Vertical Depth: 3598 feet

Operator License No.: 32819
Op Name: BAIRD OIL COMPANY LLC
Address: 113 W MAIN PO BOX 428
LOGAN, KS 67646

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3597		450 SX
SURF	8.625	219		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/14/2017 10:00 AM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Rcvd. from: BRYANT REESE Company: BAIRD OIL COMPANY LLC Phone: (785) 689-7456

Proposed Plugging Method: Ordered 280 sx 60/40 pozmix 4% gel cement, 13 sx gel (100 # bags) and 300 # hulls.
Port Collar at 1685' w/240 sx cement.
Production perforations: 3307' - 3310' and 3568' - 3571'.

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/14/2017 11:00 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 5 1/2" casing and pumped 50 sx cement w/200 # hulls followed by 13 sx gel, then pumped 185 sx cement w/100 # hulls. Topped off with 10 sx cement. Hooked to 8 5/8" x 5 1/2" annulus and pumped 10 sx cement. Shut in pressure 300 psi.

GPS: 39.42938N -099.59455W

Perfs:

Top	Bot	Thru	Comments
3568	3571		
3307	3310		

Remarks: GLOBAL CEMENTING TICKET # 2953

Plugged through: CSG

INVOICED

AUG 2 2 2017

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

KCC WICHITA

JUL 20 2017

RECEIVED

JUN 16 2017