

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-23731-00-00  
Spot: W2SEWNE Sec/Twnshp/Rge: 9-28S-3E  
990 feet from N Section Line, 1880 feet from E Section Line  
Lease Name: HOOPER Well #: C-1  
County: BUTLER Total Vertical Depth: 3128 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, LLC  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3126		70 SX
SURF	8.625	215		135 SX
T1	2.875	2850		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/29/2017 8:00 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Rcvd. from: R. A. (DICK) SCHREMMER Company: GRESSEL OILFIELD SERVICE, LLC Phone: (316) 524-1225

Proposed  
Plugging  
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: JERRY SPARLING WitnessType: NONE  
Date/Time Plugging Completed: 06/29/2017 2:45 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE, SET CIBP @ 3,000', DUMP BAILED 2 SXS CEMENT ON TOP OF PLUG. PERFORATED SQUEEZE HOLES 265'-266' (4 HOLES). RIH W/ TUBINB @ 270', COPELAND ACID MIXED & PUMPED 80 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. CEMENT CIRCULATED. CEMENT TICKET #44912.

Perfs:

Top	Bot	Thru	Comments
3069	3071	CSG	Simpson

INVOICED  
AUG 22 2017

Remarks: COMPLAINT

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER  
(TECHNICIAN)