

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-191-20942-00-00
Spot: NWNWSESW Sec/Twnshp/Rge: 25-31S-2E
1119 feet from S Section Line, 3682 feet from E Section Line
Lease Name: HOLT Well #: 4
County: SUMNER Total Vertical Depth: 2653 feet

Operator License No.: 35191
Op Name: BUFFALO OIL & GAS, LLC
Address: 119 N. MICHIGAN ST. PO BOX 6
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1850		
PROD	5.5	2653		150 SX
SURF	8.625	219		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/23/2017 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Revd. from: DON SHORT Company: BUFFALO OIL & GAS LLC Phone: (620) 218-1809

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX WitnessType: PARTIAL
Date/Time Plugging Completed: 05/24/2017 6:00 PM KCC Agent: DAN FOX

Actual Plugging Report:

PLUGGED BACK DEPTH WAS 1850', RAN TUBING TO BOTTOM AT 1800' AND PUMPED 35 SX OF COMMON CEMENT WITH 3% CC AND 100 LBS OF HULLS. LET CEMENT SET UP AND RAN BACK IN WITH SAND-LINE AND TAGGED TOP OF BOTTOM PLUG AT 1680'. CASING STOOD FULL OF FLUID FOR 15 MINS WITH NO DROP. PERFORATED 5.5" AT 300' RAN IN TUBING TO 300' ESTABLISHED CIRCULATION AND PUMPED 140 SX OF A 60/40 POS-MIX WITH 2% GEL TO SURFACE. COPELAND ACID & CEMENT TICKET #44943. CASING STOOD FULL, JOB COMPLETE.

Perfs:

Top	Bot	Thru	Comments
1832	1836		


INVOICED
AUG 22 2017

Remarks: NOTE: WELL WAS PLUGGED UNDER COMPLIANCE AGREEMENT DOCKET #17-CONS-3659-CMSC

Plugged through: TBG

District: 02

Signed


(TECHNICIAN)

✓st