

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-19798-00-00
Spot: SESE Sec/Twshp/Rge: 29-23S-13E
660 feet from S Section Line, 660 feet from E Section Line
Lease Name: NORTH DILLINGER Well #: 2H
County: GREENWOOD Total Vertical Depth: 1747 feet

Operator License No.: 34827

Op Name: C3OIL, LLC

Address: 600 ARROWHEAD DR
NEW STRAWN, KS 66839

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	3	1740		265 SX
SURF	7	41		9 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 07/03/2017 12:00 PM

Plug Co. License No.: 33413

Plug Co. Name: TITUS WELL SERVICE LLC

Proposal Revd. from: CHRIS HAAS

Company:

Phone: (913) 515-5329

Proposed Plugging Method: Run 2 1/16 to TD of well pump 65 sks of cement to top of well

Plugging Proposal Received By: MICHAEL HEFFERN

Witness Type: NONE

Date/Time Plugging Completed: 07/03/2017 1:30 PM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

ran tubing to 906', pumped 47 sxs cement to surface

Top	Bot	Thru	Comments
1735	1741		

RECEIVED
KCC DIST # 3
JUL 10 2017
CHANUTE, KS

MH

INVOICED


AUG 23 2017

Remarks:

Plugged through: TBG

District: 03

Signed Michael Heffern
(TECHNICIAN)



250 N. Water, Ste 200 - Wichita, Ks 67202

HURRICANE SERVICES INC

104 Prairie Plaza Parkway - Garnett, Ks 66032

Customer:	C3 Oil, LLC	Customer Name:	Chris Haas	Ticket No.:	100851
Address:	600 Arrowhead Dr.	Contractor:		Date:	7/3/2017
City, State, Zip:	New Strawn, KS 66839	Job type:	P&A - Old Well	Well Type:	Oil - Old Well
Service District:	Madison	Well Details:	Sec: 29	Typ:	23S R: 13E
Well name & No.:	North Dillinger #2H	Well Location:	Virgil	County:	Greenwood
				State:	KS
Equipment #	Driver	TRUCK CALLED			AM PM TIME
29	C. McGown	ARRIVED AT JOB			AM PM 8:10
201	K. Noeller	START OPERATION			AM PM 8:20
202	M. Watts	FINISH OPERATION			AM PM 9:10
111	JP Gullick	RELEASED			AM PM 9:15
		MILES FROM STATION TO WELL			17

Plug old well - held safety mtg; 2 1/16 IJ tubing ran to 906' inside 3 1/2" liner cemented to surface per C. Haas; rig up to tubing, break circulation with 2 bbl fresh water; mix & pump 60/40 POZ w/4% gel down tubing, good cement returns to surface, shut down to TOOH w/tubing, mix additional cement and top off well, wash tools & tubing, rig down.

Product/Service Code	Description	Unit of Measure	Quantity	List Price/Unit	Gross Amount	Net Amount
C020	Cement Pump	ea	1.00	\$675.00	\$675.00	\$513.00
C001	Heavy Equip. One Way	mi	17.00	\$3.25	\$55.25	\$41.99
CP009	60/40 Pozmix Cement	sack	47.00	\$12.85	\$603.95	\$459.00
CP013	Bentonite Gel	lb	162.00	\$0.30	\$48.60	\$36.94
C004	Minimum Ton Mile Charge	ea	1.00	\$300.00	\$300.00	\$228.00
T003	Vacuum Truck 80 bbl	hr	2.00	\$84.00	\$168.00	\$127.68
	City Water	gal	3,300.00	\$0.013	\$42.90	\$32.60

TERMS: Cash in advance unless Hurricane Services Inc. (HSI) has approved credit prior to sale. Credit terms of sale for approved accounts are total invoice due on or before the 30th day from the date of invoice. Past due accounts may pay interest on the balance past due at the rate of 1 1/2% per month or the maximum allowable by applicable state or federal laws if such laws limit interest to a lesser amount. In the event it is necessary to employ an agency and/or attorney to affect the collection of said account, Customer hereby agrees to pay all fees directly or indirectly incurred for such collection. In the event that Customer's account with HSI becomes delinquent, HSI has the right to revoke any and all discounts previously applied in arriving at net invoice price. Upon revocation, the full invoice price without discount will become immediately due and subject to collection. Prices quoted are estimates only and are good for 30 days from the date of issue. Pricing does not include federal, state, or local taxes, or royalties and stated price adjustments. Actual charges may vary depending upon time, equipment, and material ultimately required to perform these services. Discount rate is based on 30 days net payment terms or cash.

DISCLAIMER NOTICE:
This technical data is presented in good faith, but no warranty is given by and H.S.I. assumes no liability for advice or recommendations made concerning results to be obtained from the use of any product or service. The information presented is HSI best estimate of the actual results that may be achieved and should be used for comparison purposes and make no guarantee of future production performance. Customer warrants that well and all associated equipment in acceptable condition to receive services by H.S.I. Likewise, the customer will guarantee proper operational care of all customer owned production and associated equipment, while H.S.I. is on location performing services which could adversely affect the performance of such services. Authorization below acknowledges receipt and acceptance of all terms and conditions stated above.

Gross: \$ 1,893.70		Net: \$ 1,439.21
Total Taxable	\$ -	Tax Rate:
Frac and Acid service treatments designed with intent to increase production on newly drilled or existing wells are not taxable.		Sale Tax: \$ -
		Total: \$ 1,439.21
Date of Service:	7/3/2017	
HSI Representative:	C. McGown	
Customer Comments:		

X _____
CUSTOMER AUTHORIZED AGENT