

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-25448-00-00
Spot: NESWSESW Sec/Twnshp/Rge: 20-30S-17E
453 feet from S Section Line, 3606 feet from E Section Line
Lease Name: SML Well #: 2
County: WILSON Total Vertical Depth: 1083 feet

Operator License No.: 34769 String Size Depth (ft) Pulled (ft) Comment
Op Name: CHEROKEENRG LLC PROD 4.5 1060 195 SX
Address: 112 SOUTH 5TH STREET P.O. BOX 111 SURF 8.625 21 4 SX
NEODESHA, KS 66757

Well Type: GAS UIC Docket No: Date/Time to Plug: 06/28/2017 12:00 PM
Plug Co. License No.: 31696 Plug Co. Name: CUNNINGHAM CRUDE, A GENERAL PARTNERSHIP
Proposal Rcvd. from: PAM SCHULTZ Company: CHEROKEE NRG LLC Phone: (620) 432-1840

Proposed Plugging Method: Pull rod and tubing out of hole, run tubing to bottom, gel hole, spot 50' plug (5 sacks), pull up to 500', spot 50' plug (5 sacks), pull up to 225', cement to surface, pull tubing out, top off cement, cut wellhead off below plow depth and restore location.

Plugging Proposal Received By: ALAN DUNNING Witness Type: PARTIAL
Date/Time Plugging Completed: 06/28/2017 3:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A one inch cement string was washed down to 1030 feet and the hole gelled. A 50 ft cement plug was then spotted at TD. The cement string was raised to 500 ft and a 2nd 50 ft cement plug was spotted. The cement string was raised to 225 ft and filled to surface with cement. A total of 28 sacks of portland cement were used to plug well.

Perfs:

Top	Bot	Thru	Comments
625	633		
605	633		

RECEIVED
KCC DIST # 3
JUL 10 2017
CHANUTE, KS

AD

INVOICED

AUG 23 2017

Remarks:

Plugged through: CSG

District: 03

Signed Alan M. Dunning
(TECHNICIAN)