

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-205-25447-00-00  
Spot: NENWNESW Sec/Twnshp/Rge: 20-30S-17E  
2322 feet from S Section Line, 3618 feet from E Section Line  
Lease Name: SML Well #: 1  
County: WILSON Total Vertical Depth: 1023 feet

Operator License No.: 34769 String Size Depth (ft) Pulled (ft) Comment  
Op Name: CHEROKEENRG LLC PROD 4.5 995 172 SX  
Address: 112 SOUTH 5TH STREET P.O. BOX 111 SURF 8.625 21 4 SX  
NEODESHA, KS 66757

Well Type: GAS UIC Docket No: Date/Time to Plug: 06/29/2017 12:00 PM  
Plug Co. License No.: 31696 Plug Co. Name: CUNNINGHAM CRUDE, A GENERAL PARTNERSHIP  
Proposal Rcvd. from: PAM SCHULTZ Company: CHEROKEE NRG LLC Phone: (620) 432-1840

Proposed Pull rod and tubing out of hole, run tubing to bottom, gel hole, spot 50' plug (5 sacks), pull up to 500', spot 50' plug (5  
Plugging sacks), pull up to 225', cement to surface, pull tubing out, top off with cement, cut wellhead off below plow depth and  
Method: restore location.

Plugging Proposal Received By: LARRY MARCHANT WitnessType: PARTIAL  
Date/Time Plugging Completed: 06/29/2017 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A one inch cement string was washed down to 910 feet and the hole gelled. A 50 ft cement plug was placed at TD. The cement string was pulled to 500 ft and a 50 ft cement plug spotted. The cement string was pulled to 225 ft and the well filled to top with cement. A total of 28 sacks of portland cement were used to plug well.

Perfs:

Top	Bot	Thru	Comments
979	984		

RECEIVED  
KCC DIST # 3  
JUL 10 2017  
CHANUTE, KS

AD

INVOICED

AUG 23 2017

Remarks:

Plugged through: CSG

District: 03

Signed Alan Dunning  
(TECHNICIAN)