

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-20159-00-01
Spot: S2 Sec/Twushp/Rgc: 24-34S-12W
1305 feet from S Section Line, 2654 feet from E Section Line
Lease Name: CHRISTENSEN Well #: 1-24
County: BARBER Total Vertical Depth: 4760 feet

Operator License No.: 33235
Op Name: CHIEFTAIN OIL CO., INC.
Address: 101 S. 5TH ST. PO BOX 124
KIOWA, KS 67070

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4680		WITH 2 SX CMT
COND	13.375	118		WITH 300 SX CMT
PROD	5.5	4751	2500	WITH 150 SX CMT
SURF	8.625	332		WITH 200 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 07/10/2017 12:00 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Revd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SET CIBP @ 4680' WITH 2 SX CMT. PLUG AT 660' WITH 10 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/10/2017 1:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4680' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 664' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 362' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 40 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4724	4730	CSG	

INVOICED
AUG 23 2017

Remarks: USED 60/40 POZMIX 4% GEL BY HURRICANE SERVICES.

Plugged through: TBG

District: 01

Signed Steve Pfeifer
(TECHNICIAN)

RECEIVED
JUL 17 2017
KCC DODGE CITY