

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-06516-00-00
Spot: SWSW Sec/Twnshp/Rge: 33-13S-15W
660 feet from S Section Line, 660 feet from W Section Line
Lease Name: CARTER Well #: 0-8
County: RUSSELL Total Vertical Depth: 3048 feet

Operator License No.: 31428
Op Name: CRAWFORD, JEFF DBA LONESTAR OIL
Address: PO 205
GORHAM, KS 67640

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	4.5	2655		
PROD	5.5	3048		200 SX
SURF	8.58	240		130 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/08/2017 8:30 AM
Plug Co. License No.: 34410 Plug Co. Name: AMERICAN PULLING SERVICE
Proposal Rcvd. from: JEFF CRAWFORD Company: CRAWFORD, JEFF DBA LONESTAR Phone: (785) 735-4585

Proposed Plugging Method: Ordered 250 sx 60/40 pozmix 4% gel cement w/200 # hulls.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/08/2017 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 300', 950' and 1450'. Ran tubing to 2700' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 1450' and pumped 90 sx cement. Circulated cement to pit. POOH. Hooked to casing and pumped 25 sx cement at 350 psi. Hooked to braden head and pumped 10 sx cement at 150 psi. Casing stayed full. Total of 225 sx cement w/100 # hulls used to plug.

GPS: 38.87275 -099.00037

Perfs:

INVOICED
AUG 23 2017

Remarks: GLOBAL CEMENTING TICKET # 2966

Plugged through: TBG

District: 04

Signed Ray A Dinkel

KCC WICHITA

(TECHNICIAN)

CM

JUN 13 2017

JUL 20 2017

RECEIVED