

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-159-20803-00-00  
Spot: NWSWNE Sec/Twnshp/Rge: 20-18S-6W  
1650 feet from N Section Line, 2310 feet from E Section Line  
Lease Name: HERRICK Well #: 1  
County: RICE Total Vertical Depth: 3400 feet

Operator License No.: <u>30931</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>DAYSTAR PETROLEUM, INC.</u>	PROD	4.5	3325		250 SX
Address: <u>522 N. MAIN ST PO BOX 560</u>	RBP	4.5	3264		
<u>EUREKA, KS 67045</u>	SURF	8.625	209		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/28/2017 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: NONE  
Date/Time Plugging Completed: 04/28/2017 2:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, PULL RODS AND TUBING. RUN TUBING TO 3160' AND PUMP 50 SX'S COMMON WITH 100#'S HULLS. PERFORATE AT 950', 600', AND 250'. RUN TUBING TO 950' AND PUMP 35 SX'S COMMON WITH 2% CC, PULL TUBING TO 550' AND WAIT AWHILE. ATTEMPT TO TAG CEMENT, COULD NOT. RUN TUBING BACK TO 950' AND PUMP 35 MORE SX'S COMMON WITH 2% CC. PULL TUBING UP TO 550' AND WAIT AWHILE. TAGGED CEMENT AT 600'. RUN TUBING TO 580' AND PUMPED 35 SX'S COMMON WITH 2% CC. PULL TUBING TO 250' AND PUMPED 100 SX'S 60-40 POZ, 4% GEL, GETTING CEMENT CIRCULATION TO SURFACE. PULL TUBING OUT AND TOPPED OFF WITH 30 SX'S.

Perfs:

Top	Bot	Thru	Comments
3205	3251	CSG	
2778	3251	CSG	

INVOICED  
AUG-24 2017

Remarks: COPELAND CEMENT #C-44771. GRESSELL PERF TICKET #1533.

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

125