

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-24624-00-00
Spot: NWSENE Sec/Twnshp/Rge: 10-13S-17W
3630 feet from S Section Line, 990 feet from E Section Line
Lease Name: CATHERINE UNIT Well #: 1-5
County: ELLIS Total Vertical Depth: 3553 feet

Operator License No.: 7064
Op Name: DORZWEILER, LEO R. DBA CATTLEM
Address: 2260 CATHERINE RD
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3545		500sx
SURF	8.625	192		135 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/06/2017 9:30 AM
Plug Co. License No.: 99975 Plug Co. Name: COMPANY SERVICING TOOLS
Proposal Rcvd. from: LEO R DORZWEILER Company: DORZWEILER, LEO R. DBA CATTLE Phone: (785) 623-6847

Proposed Plugging Method: 5 1/2" casing cemented bottom to surface w/500 sx cement.
Production perforations: 3296' - 3553'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/06/2017 1:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

Ran tubing to 3000'. Quality Oilwell Cementing pumped 16 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 1600' and pumped 80 sx cement w/200 # hulls. Pulled tubing to 800' and pumped 75 sx cement w/100 # hulls. Cement circulated. PTOH. Topped 5 1/2" casing with 10 sx cement. Checked backside and had instant pressure.


INVOICED
AUG 29 2017

Remarks: QUALITY OILWELL CEMENTING TICKET # 1886

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

CM

KCC WICHITA

JUL 20 2017

RECEIVED

JUL 16 2017