

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-20210-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 18-12S-17W
301 feet from S Section Line, 2429 feet from E Section Line
Lease Name: SCHMEIDLER B Well #: 2
County: ELLIS Total Vertical Depth: 3666 feet

Operator License No.: 34434
Op Name: EDISON OPERATING COMPANY LLC
Address: 8100 E. 22ND ST. N., BLDG 1900
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3659		125 SX
SURF	8.625	210		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/14/2017 10:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: CURTIS KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/800 # hulls.
PBTD: 3300'
Perforations: 3320' - 3324', 3461' - 3464' and 3652' - 3666'.
CIBP at 3300'

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/14/2017 4:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Kelso Knocked out bridge plug at 3300'. Pioneer perforated at 1850', 1350' and 840'. Kelso ran in hole with tubing to 3650' and pumped 100 sx cement w/300 # hulls mixed in. Pulled tubing to 2650' and pumped 100 sx cement w/200 # hulls mixed in. Pulled tubing to 1650' and pumped 190 sx cement w/100 # hulls mixed in to circulate cement to pit. Pulled tubing. Rigged to 5 1/2" casing and pumped 15 sx cement to pressure with 200 psi. Shut in pressure 200 psi. Hooked to 8 5/8" surface casing with instant pressure.

Perfs:

Top	Bot	Thru	Comments
3652	3666		
3461	3464		
3320	3324		

Remarks: COPELAND CEMENTING CO TICKET # 45147

Plugged through: TBG

District: 04

Signed
KCC WICHITA


(TECHNICIAN)

CM

JUL 20 2017

RECEIVED

JUL 17 2017

Form CP-2/3

INVOICED
AUG 29 2017