

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-093-20557-00-00  
Spot: NW Sec/Twnshp/Rge: 32-22S-37W  
3364 feet from S Section Line, 3937 feet from E Section Line  
Lease Name: M F POWERS UNIT C Well #: 1  
County: KEARNY Total Vertical Depth: 3037 feet

Operator License No.: 34434  
Op Name: EDISON OPERATING COMPANY LLC  
Address: 8100 E. 22ND ST. N., BLDG 1900  
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2785		WITH 10 SX CMT
PROD	4.5	3037	0	WITH 500 SX CMT
SURF	8.625	936		WITH 500 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/11/2017 11:00 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: CIBP @ 2785' & 2 SX CMT. PUMP 65 SX CMT VIA TBG AT 2100' TO 1100' WITH HULLS TO SHUT OFF GLORIETTA LEAK. RUN CBL TO DETERMINE TOC AFTER LOADING HOLE. PERFORATE BELOW SURFACE CASING AT 960'. SPOT 50 SX CMT HALF IN & HALF OUR AT 960'. PERFORATE AT 500' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/12/2017 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2785' WITH 10 SX CMT ON TOP OF CIBP. SPOT 65 SX CMT WITH 100# HULLS AT 2094' TO 1100'. TOOH WITH TBG & LOAD HOLE WITH WATER. SDFN, 7/12/17; TAG TOC IN 4 1/2" CASING AT 1176'. RAN CBL. FOUND TOC BEHIND 4 1/2" CASING AT 640'. PERFORATE 4 HOLES AT 600'. SPOT 20 SX CMT PLUG AT 964' TO 700'. CIRCULATE CMT TO SURFACE IN THE 4 1/2" CASING & UP THE ANNULUS THROUGH PERFS AT 600' USING 200 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2810	2948		


Remarks: \*\*COMPLIANCE ISSUE: DENIED TA HIGH FL\*\* USED CLASS A COMMON CEMENT BY BASIC.

Plugged through: TBG

INVOICED  
AUG 29 2017

District: 01

Signed



(TECHNICIAN)

RECEIVED  
JUL 21 2017  
KCC DODGE CITY

