

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-047-21385-00-00
 Spot: S2SE Sec/Township/Rge: 22-24S-16W
721 feet from S Section Line, 1289 feet from E Section Line
 Lease Name: SKALSKY A Well #: 1-22
 County: EDWARDS Total Vertical Depth: 4470 feet

Operator License No.: 5056
 Op Name: F. G. HOLL COMPANY L.L.C.
 Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4210		WITH 2 SX CMT
PROD	4.5	4468	0	WITH 225 SX CMT
SURF	8.625	398		WITH 260 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 07/03/2017 10:00 AM
 Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
 Proposal Rcvd. from: ROB LONG Company: FG HOLL Phone: (620) 793-0915

Proposed Plugging Method: SET CIBP @ 4210' WITH 2 SX CMT. PERFORATE AT 1110' WITH 10 SX GEL & 50 SX CMT. PERFORATE AT 450' WITH CMT TO 0'.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
 Date/Time Plugging Completed: 07/05/2017 12:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

7/3/17: CIBP SET AT 4210' & TOPPED WITH 2 SX CMT. PERFORATE 2 SHOTS/FT AT 1110' & 450'. TH WITH 2 7/8" TBG TO 1110' & ESTABLISH CIRCULATION WITH FRESH WATER. PUMP 10 SX GEL FOLLOWED BY 50 SX CMT WITH 200# HULLS IN LAST 25 SX. PULL TBG TO 450' & ESTABLISH CIRCULATION WITH FRESH WATER. PUMP 65 SX CMT TO FILL 4 1/2" CASING. PUMP 160 SX CMT TO FILL ANNULUS BUT NO RETURNS. LET CMT SET WHILE WATER TRUCK WENT FOR MORE WATER. WATER TRUCK RETURNED & REMAINING 65 SX CMT ON LOCATION WAS PUMPED WITHOUT RETURNS. SHUT DOWN. 7/5/17: CMT WAS TAGGED WITH TBG AT 217' INSIDE 4 1/2" CASING & PRESSURED UP TO 500 PSI. USED 30 SX CMT TO FILL 4 1/2" CASING TO SURFACE. 1" TBG WAS RUN INTO ANNULUS TO 337' & 85 SX CMT WAS PUMPED TO FILL ANNULUS TO SURFACE. CMT HOLDING AT SURFACE.

Perfs:

Top	Bot	Thru	Comments
4260	4298		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: TBG

District: 01

Signed Kenny Scofield
 (TECHNICIAN)

RECEIVED
 JUL 17 2017
 KCC DODGE CITY