

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-20294-00-01

Spot: SENENW

Sec/Twnshp/Rge: 26-16S-29W

4199 feet from S Section Line, 3003 feet from E Section Line

Lease Name: JAMES

Well #: 2

County: LANE

Total Vertical Depth: 4580 feet

Operator License No.: 6170

Op Name: GLOBE OPERATING, INC.

Address: PO BOX 12

GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4100		WITH 2 SX CMT

CIBP		4315		
PROD	5.5	4579	0	WITH 25 SX CMT

SURF	8.625	240		WITH 175 SX CMT
------	-------	-----	--	-----------------

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 07/17/2017 9:00 AM

Plug Co. License No.: 32970

Plug Co. Name: H-D OILFIELD SERVICE, INC.

Proposal Revd. from: JEFF WERTH

Company: H-D OILFIELD SERVICE, INC.

Phone: (620) 792-7607

Proposed Plugging Method: SET CIBP 50' ABOVE PERFS. LOAD HOLE WITH WATER & LOG HOLE TO SEE IF WELL HAS BEEN CEMENTED ON TOP STAGE. IF IT HAS NOT THEN PERFORATE AT 2230' & SPOT 50 SX CMT. THEN PERFORATE AT 1250' & PUMP 80 SX CMT OVER CASING VOLUME. IF DOES NOT CIRCULATE PUMP 150 SX CMT DOWN BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 07/17/2017 5:30 PM

KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4100' WITH 2 SX CMT. LOADED HOLE WITH 96 BBL FRESH WATER. RUN BOND LOG. FOUND CMT FROM 2100' TO 250'. RUN TBG TO 2200' & SPOTTED 50 SX CMT. PULLED TBG TO 1200' & PUMPED 155 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 15 SX CMT. TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURED TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
4128	4269		

INVOICED
AUG 29 2017

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed

Michael Maier
SA

(TECHNICIAN)

RECEIVED

JUL 18 2017

KCC DODGE CITY