

KANSAS

FORM CP-3
Rev. 10-8-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-19520,520

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Plains Resources
HELSO CASING PULLING

Complete Address BOX 176 CHASE, HANS. 67524

Lease Name MOLLENTAMP Well No. #1

Location C-SW Sec. 18 Twp. 15 Rge. 24 (East)(West)

County TREBO Total Depth 4801 FT

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor HELSO CASING PULLING

Address BOX 176 CHASE, HANS. 67524 License No. 683

Operation Completed: Hour: 1:45 PM Day: 31 ST Month: DEC Year: 1981

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8" - 219 FT SP. CUM 1/200 ST CMT, → 5 1/2" SET @ 4800 FT 1/200 ST CMT.

PLUG. BACK T.O. 4644 FT → PERF'S. TOP 4038 FT

HELSO CASING SANDED BOTTOM TO 3950 FT AND 1/5 ST CMT.

SHOT CASING 5 TIMES, RECOVERED 2976 FT.

ORDERED 140 ST 50/50 FORMIX 4% GEL → 3% CA-CL, → 27 ST GEL, → 5 ST HULL'S + 8 5/8" PLUG.

PUMPED IN 8 5/8" CASING WITH PUMP TRUCK.

PMT. IN, 4 ST HULL'S, → 15 ST GEL, → 1 ST HULL'S, → 70 ST CMT. → 12 ST GEL.

RELEASED PLUG AND 70 ST CMT, → MAX P.S.F. PRESSURE 200 ^{LB}

Amount of Surface Casing: 219 FT CEMENTED BY ALLIED CMT.

I hereby certify that the above plugging instructions were given as herein stated. RECEIVED STATE CORPORATION COMMISSION

INVOICED

DATE 1-21-82

INV. NO. 9067-u

JAN - 5 1982

CONSERVATION DIVISION
Wichita, Kansas

Signed: Marian Schmidt
Conservation Division Agent
+ Dennis Hamel