



GEORGE DOCKING Governor
 MARION BEATTY Chairman
 HARRY G. WILES Commissioner
 RICHARD C. BYRD Commissioner
 RAYMOND B. HARVEY Secretary
 CLYDE E. MILLIGAN Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS
 JEWEL M. OGDEN, Director

Jewel M. Ogden, Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date Nov 3, 1960, authorized the following plugging operation:

Operator's Full Name: Sinclair Oil Co

Complete Address: Chase Kans.

Lease Name: A. E. Montgomery Well No. 1

Location: 6608-6608-7th Sec. 15 Twp. 15 Rge. 24 (E) (W)

County: Orego Total Depth: 4723

Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Operator was instructed to plug well as follows:

Jet Pitts circulate hole with heavy mud, set cementing plug
 at 600 ft. and displace 20 sac cement thru drill pipe,
 heavy mud to 240 ft, set cementing plug and displace 20 sac
 cement, heavy mud to 40' set and tie cementing plug in place
~~with wire and dump $\frac{1}{2}$ sac dry bulls and 10 sac cement, cementing~~
~~to base of cellar.~~

STATE CORPORATION COMMISSION
 NOV 16 1960

CONSERVATION DIVISION
 Wichita, Kansas

11-16-1960

Very truly yours,
 Gilbert P. Leiker

Signed: Gilbert P. Leiker
 Conservation Division Agent