

15.195.20201.00.00

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 6 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name The Cherokee and Pittsburg Coal and Mining Company,

Complete Address 900 Polk Street, Amarillo, Texas.

Lease Name Harm Schneider Well No. 1

Location CSW NE
1980' FNL & 1980' FEL of Sec. 21 Twp. 15 Rge. (E) (W) 23

County Trego Total Depth 4621'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Sterling Drilling Company.

Address Box #129, Sterling, Kansas. License No.

Operation Completed: Hour 11:00 AM Day 2 Month 1 Year 1972

The above well was plugged as follows:

372'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 675'.

Circulated hole with heavy mud. Pulled DP to 900' and displaced 110 Cu. Ft. cement
thru DP from 900' to 575'. Pulled DP to 400' and displaced 30 Cu. Ft. cement thru
DP from 400' to 325'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. G. Nichols
Well Plugging Supervisor

DATE 1-11-72

INV. NO. 4932-42