

*16*  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

DEC 15 1965

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name D & D Drilling Company, Incorporated,

Complete Address: 307 Schweiter Building, Wichita, Kansas.

Lease Name \_\_\_\_\_ Price \_\_\_\_\_ Well No. 1

Location CSE-NW Sec. 15 Twp. 15 Rge. (E) (W) 21

County Trego Total Depth 4160

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Above

Address: \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour 11:00AM Day 12 Month 12 Year 1965

The Above well was plugged as follows:

231'--8 5/8" Surface pipe, cement circulated with 200 Sx.

Circulated hole with heavy mud, set plug @ 540' and displaced 20 Sx.

cement thru DP. Heavy mud to 220', set plug with 1/4 sack hulls and dis-

placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack

hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *H. L. Nichols*  
Well Plugging Supervisor

DATE 12/15/65

INV. NO. 2419-W