

15.195.20109.00.00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 3 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name John O. Farmer, Incorporated,

Complete Address: 370 West Wichita Avenue, Russell, Kansas.

Lease Name Brenner Well No. B-3

Location CNE-NE Sec. 13 Twp. 15 Rge. (E) (W) 21

County Trego Total Depth 3906'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 12:00M Day 1 Month 3 Year 1969

The Above well was plugged as follows:

167'--8 5/8" Surface casing, cement circulated with 115 Sx.
Top of Dakota section @ 400'.

Circulated hole with heavy mud. Pulled DP to 625' and displaced 100 Sx. cement thru
DP from 625' to 300'. Pulled DP to 185' and displaced 20 Sx. cement thru DP from 185'
to 120'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. D. J. J. J.
Well Plugging Supervisor

DATE 3/3/69
INV. NO. 9400-W