

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 7 1965

CONSERVATION DIVISION
Wichita, Kansas

5-9-1965

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Buttes Gas & Oil Co., and Omega Drilling, Inc.,

Complete Address: 427 Union Center, Wichita, Kansas.

Lease Name Alois Engel Well No. 1

Location CSE-NE Sec. 6 Twp. 15 Rge. (E) (W) 21

County Trego Total Depth 4215

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Omega Drilling, Incorporated,

Address: 427 Union Center, Wichita, Kansas. License No.

Operation Completed: Hour 7:30PM Day 3 Month 5 Year 1965

The Above well was plugged as follows:

615'--8 5/8" Surface pipe, cement circulated.

Circulated hole with heavy mud, set plug @ 600' and displaced 20 Sx.

cement thru DP. Heavy mud to 240', set plug with 1/2 sk. hulls and dis-

placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack

hulls and 10 Sx. cement to bottom of cellar.

(Cementing operations performed by the Halliburton Co.)

I hereby certify that the above well was plugged as herein stated.

Signed: H. L. Nichols
Well Plugging Supervisor

DATE 5/9/65

INV. NO. 1120-W