

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 20 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Donald C. Slawson,

Complete Address 408 One-Twenty Building, Wichita, Kansas.

Lease Name Messier Well No. A-3

Location 150' East of CNW-SW Sec. 14 Twp. 14 Rge. (E) (W)22

County Trego Total Depth 4219'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Slawson Drilling Company, Incorporated,

Address 408 One-Twenty Building, Wichita, Ks. License No.

Operation Completed: Hour 9:00 PM Day 14 Month 3 Year 1972

The above well was plugged as follows:

349'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakotasection @ 525'.

Circulated hole with heavy mud. Pulled DP to 750' and displaced 100 Sx. cement thru
DP from 750' to 425'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. J. Doherty
Well Plugging Supervisor

DATE 3/24/72

INV. NO. 5402-10