

KANSAS

*Handwritten mark*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 29 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Donald C. Slawson Oil Producer,

Complete Address 408 One-Twenty Building, Wichita, Kansas.

Lease Name Massier Well No. A-2

Location CSE-NW Sec. 11 Twp. 11 Rge. (E) (W) 22

County Grego Total Depth 4265'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Slawson Drilling Company, Incorporated,

Address 408 One-Twenty Building, Wichita, Kansas. License No.       

Operation Completed: Hour 5:30 PM Day 26 Month 3 Year 1971

The above well was plugged as follows:

249'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 500'.

Circulated hole with heavy mud. Pulled DP to 725' and displaced 100 Sx. cement thru  
DP from 725 to 400'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from 275'  
200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of  
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. L. Nichols*  
Well Plugging Supervisor

DATE 3/31/71  
INV. NO. 3482-11