


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Trego County. Sec. 30 Twp. 14 Rge. (E) 24 (W)
Location as "NE/CNW/SW" or footage from lines NE/SW/SE
Lease Owner National Associated Petroleum Company
Lease Name Arthur O'Toole B Well No. 1
Office Address Fifth Floor Ritz Building Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4-6 19 57
Application for plugging filed 4-6 19 57
Application for plugging approved 4-6 19 57
Plugging commenced 4-6 19 57
Plugging completed 4-6 19 57
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	240'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Filled hole to 240' with heavy mud, let bottom plug with 1/3 sack hulls, 20 sacks cement thru drill pipe--Filled to 40' with heavy mud. Set top plug with 1/3 sack hulls-10 sacks cement--Filled to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lewis Drilling Company
Address 915 Union Center, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
J. F. Hambright (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. F. Hambright
915 Union Center, Wichita 2, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of April, 19 57

My commission expires 8-20-60

A. P. Derrington
Notary Public.
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC. 30 T. 14 R. 24w
BOOK PAGE 4 LINE 32

APR 15 1957
CONSERVATION DIVISION

4-15-1957

WELL LOG

COMPANY National Associated Petroleum Company

SEC. 30 T. 14 R. 24W
LOC. NE/SW/SE

FARM Arthur O'Toole B NO. 1

TOTAL DEPTH 4385'

COMM. 3-22-57


COMP. 4-6-57

COUNTY Trego KANSAS

SHOT OR TREATED

CONTRACTOR Lewis Drilling Company

ISSUED



CASING

20	10
15	8 5/8" -- 240'
12	6
13	5

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

0-240	Surface soil and shale
240-1360	Shale
1360-1480	Red beds
1480-1525	Anhydrite
1525-2300	Shale
2300-3550	Shale and Lime
3550-4385	Lime
4385	Total Depth

PLUGGING
 FILE SEC. 30 T. 14 R. 24W
 BOOK PAGE 4 LINE 32
 ss:

State of Kansas

County of Sedgwick

RECEIVED
 REGISTRATION COMMISSION
 APR 15 1957

I, J. Fred Hambright of the Lewis Drilling Wichita Falls Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Arthur O'Toole B#1 well.

Subscribed and sworn to before me this 9 day of April 19 57

My Commission Expires: 8-20-60

A. R. Derrington
 A. R. Derrington NOTARY PUBLIC