


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Trego County, Sec. 14 Twp. 14S Rge. 22W (E) (W)
Location as "NE/CNW*SW*" or footage from lines 150' E of C NW SW
Lease Owner Donald C. Slawson
Lease Name Massier 'A' Well No. 3
Office Address Suite 408 One Twenty Building-Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 14, 1972
Application for plugging filed March 14, 1972
Application for plugging approved March 14, 1972
Plugging commenced March 14, 1972
Plugging completed March 14, 1972
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W.L. Nichols-P.O. Box 157-Morland, Kansas 67650
Producing formation Depth to top Bottom Total Depth of Well 4219 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	249'	8 5/8"	X	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug at 750' with 100 sx cement
Plug at 275' with 25 sx cement
Plug at 40'; 1/2 sac hulls; 10 sx cement
2 sx cement in rat hole

Completed at 9:00 p.m. March 14, 1972

RECEIVED
STATE CORPORATION COMMISSION
MAR 21 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Slawson Drilling Company, Inc.
Address Suite 408 One Twenty Building-Wichita, Kansas 67202


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
MAXINE V. STARR

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well filed and that the same are true and correct. So help me God.

(Signature) Maxine V. Starr
408 One Twenty Building-Wichita, Kansas
(Address)

Subscribed and sworn to before me this 20th day of March, 1972

My commission expires May 15, 1975



Linda R. Mitchell
Notary Public.

WELL LOG

Company: Donald C. Slawson
 Suite 408 One Twenty Building
 Wichita, Kansas 67202

Lease: Massier 'A' #3
 150' E of C NW SW, Sec. 14-14-22W
 Trego County, Kansas

Total Depth: 4219' Elevation: 2234 K.B.

Contractor: Slawson Drilling Company, Inc.

Commenced: March 7, 1972

Completed: March 14, 1972

Casing: 8 5/8" at 249' with 250 sx cement

0-249	Lime & Shale
249-1640	Shale & Shells
1640-1682	Anhydrite
1682-2400	Shale & Shells
2400-3094	Lime & Shale
3094-4052	Lime
4052-4097	Shale
4097-4150	Sand
4150-4219	Lime & Chert
4219	Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 21 1972
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS:
 COUNTY OF SEDGWICK)

I, Maxine V. Starr, of the Slawson Drilling Company, Inc., upon oath state that the above and foregoing is a true and correct copy of the log of the Massier 'A' #3 well.

Maxine V. Starr

 MAXINE V. STARR

Subscribed and sworn to before me this 20th day of March, 1972,

Linda R. Mitchell

 Linda R. Mitchell, Notary Public

