

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission,
800 Bittling Building
Wichita, Kansas

15.195.01533.00.00
WELL PLUGGING RECORD NOV 10 1937
OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

*Pd.
11/10/37
Hoo*

NORTH



Locate well correctly on above
Section Plat

Trego County. Sec. 12 Twp. 14S Rge. (E) 22 (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines Center SW $\frac{1}{2}$ NE $\frac{1}{2}$ SW $\frac{1}{2}$
Lease Owner Central Commercial Company
Lease Name Locker Well No. 1
Office Address Tulsa, Oklahoma
Character of Well (Completed as Oil, Gas or Dry Hole) Dry
Date, well completed October 25 193 7
Application for plugging filed October 27 193 7
Application for plugging approved October 29 193 7
Plugging Commenced October 29 193 7
Plugging Completed October 30 193 7
Reason for abandonment of well or producing formation Dry
If a producing well is abandoned, date of last production 193
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. T. Alexander
Producing formation Depth to top Bottom Total Depth of Well 473 1 Feet
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				12 $\frac{1}{2}$	160 ft.	none cemented in.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Filled with Rotary mud 473 to 700 feet. Cement Plug at 700 feet, filled with mud to 235. Cemented plug, set at 235. Filled with mud to top, cement cap on top.

*Pd.
11/10/37
Hoo*



(If additional description is necessary use BACK of this sheet)
Correspondence regarding this well should be addressed to Rose Spring Drilling Co
Address 809 Edna Singleton Bldg
Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
(employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *W. Beardmore*
Gous Kaus
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of November, 1937

My commission expires July 31, 1941

W. Beardmore
Notary Public.

NOV 10 1937

LOCKER # 1

Cor. SW $\frac{1}{4}$ NE $\frac{1}{4}$ SW $\frac{1}{4}$
 Sec. 12-14S-22W
 Trego County, Kansas

Drilled for: Central Commercial Company
 Drilled by: The Rose Spring Drilling Company

Elevation: 2229'

CASING RECORD:

12 $\frac{1}{2}$ " 122'

Drilling Commenced: September 5, 1937
 Drilling Completed: October 25, 1937

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION</u>	<u>DEPTH</u>
white lime	60	broken lime	3320
blue shale	122	shale & shells	3350
shale	160	shale	3370
shale & shells	480	sand	3380
sticky shale	650	lime	3417
shale & sand	760	shale	3427
shale	810	lime	3450
sand	885	shale	3457
sand & shale	960	lime	3480
red bed & sand	1160	shale	3500
shale & red sand	1380	hard lime	3515
shale	1370	lime	3615
shale & sand	1515	lime & flint	3640
shale	1620	lime	3690
lime	1650	sandy lime	3730
anhydrite	1686	lime	3890
shale & shells	1730	broken lime	3915
lime	1805	conglomerate	3955
shale & shells	1970	lime	3970
shale & lime	2030	conglomerate	3975
anhydrite	2050	shale & shells	3990
salt & shale	2160	lime	4010
shale	2190	coring	4014
shale & shells	2230	coring	4025
lime	2245	lime	4060
shale & shells	2271	lime & flint	4080
lime	2335	chert & shale	4090
broken lime	2420	hard chert	4100
lime & shale	2500	chert	4125
shale & shells	2520	sharp lime	4129
lime	2540	lime & chert	4138
hard lime	2560	chert	4150
lime	2670	hard lime & chert	4165
shale & lime	2750	chert	4175
broken lime	2770	lime	4179
shale	2790	coring	4188
lime	2830	coring	4194
broken lime	2960	lime	4540
lime	3025	sandy lime	4605
broken lime	3065	lime	4635
sticky shale	3090	hard lime	4652
shale	3160	lime	4665
lime	3205	hard lime	4689
broken lime	3210	lime	4715
lime	3230	lime & granite	4731 TOTAL DEPTH

STATE OF KANSAS

COUNTY OF SEDGWICK SS

PLUGS
 FILE SEC 12 14 22W
 BOOK PAGE 114 LINE 49

I, the undersigned, being duly sworn on oath, state that the above and within statement is a true and correct record and log of the well drilled on the location above described, to the best of my knowledge and belief.

Subscribed and sworn to before me this _____ day of _____ 19____

Commission Expires --

Notary Public