

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15. 195. 00997. 00. 00

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Trego County. Sec. 21 Twp. 14 Rge. 21 (W) W (W)
Location as "NE/CNW/SW" or footage from lines. Gen. S/2 SE NE
Lease Owner Woodman & Tannitti Oil Company
Lease Name Switzer Well No. 2
Office Address Box 387, Hoisington, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11-17 19 59
Application for plugging filed 11-17 19 59
Application for plugging approved 11-17 19 59
Plugging commenced 11-17 19 59
Plugging completed 11-17 19 59
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well Gilbert P. Leiker
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3945 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	168'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom plug 600' - 20 sacks
Middle plug 160' - 20 sacks
Top plug 40' - 10 sacks

RECEIVED
STATE CORPORATION COMMISSION

NOV 18 1959

CONSERVATION DIVISION
Wichita

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Woodman & Tannitti Drilling Company
Address P. O. Box 387, Hoisington, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

K. T. Woodman (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) K. T. Woodman

714 Union National Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of November, 19 59

Mildred E. Lick
Mildred E. Lick, Notary Public.

My commission expires March 15, 1961



DRILLING LOG

NOV 18 1959

CONSERVATION DIVISION
Wichita, Kansas

Company: Woodman & Iannitti Oil Company
 Lease: Switzer #2 - Cen. S/2 SE NE Sec. 21-14S-21W
 Trego County, Kansas
 Contractor: Woodman & Iannitti Drilling Company
 P. O. Box 387, Hoisington, Kansas
 Date Commenced: 11-7-59
 Date Completed: 11-17-59
 Total Depth: 3945'
 Casing: 8 5/8" set at 168' with 140 sacks quick-set cement

Figures Indicate the Bottom of the Formation

0-20	Post Rock	2165	Shale & Shells
70	Sand	3890	Lime
626	Shale	3920	Chert & Lime
645	Sand	3945	Lime
860	Shale & Sand		
1010	Red Bed & Shale		
1245	Sand		
1533	Red Bed, Shale & Shells		
1575	Anhydrite		
1775	Red Bed & Shale		

GEOLOGICAL TOPS

Elevation	2193	RB
Anhydrite	1533	660
Heebner	3498	-1305
Toronto	3519	-1326
Lansing	3535	-1342
Base/Kansas City	3794	-1601
Pennsylvania Sd.	3926	-1733
Total Depth	3945	-1752

I certify the above to be a true and correct copy of the Driller's Log and Geological Tops to the best of my knowledge and belief.

WOODMAN & IANNITTI DRILLING CO.

By:


 K. T. Woodman