


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Trego County, Sec. 18 Twp. 15S Rge. (E) 21 (W)  
Location as "NE/CNW/SW" or footage from lines C SE SE SW  
Lease Owner Sunray Mid-Continent Oil Company  
Lease Name Ward R. Philip Well No. 1  
Office Address Box 788, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed May 29 1959  
Application for plugging filed June 1 1959  
Application for plugging approved June 2 1959  
Plugging commenced May 29 1959  
Plugging completed May 29 1959  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J. Lewis Brock  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4272 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	319	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with drilling mud to 600', set wooden plug with 20 sacks cement, filled with mud to 240', set wooden plug with 1/3 sacks hulls and 15 sacks cement. Filled hole with mud to 40', 1/3 sack hulls, wooden plug and 10 sacks cement, plugging completed.

Well Log Attached.

**RECEIVED**  
STATE CORPORATION COMMISSION  
JUN 5 1959  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Halliburton Oil Well Cementing Company  
Address \_\_\_\_\_

STATE OF Kansas, COUNTY OF Barton, ss.  
N. E. Montgomery (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) N. E. Montgomery  
Box 788, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of June, 1959

My commission expires December 24, 1960 Notary Public.

PLUGGING  
FILE SEC 18 T. 15 R. 21 W  
BOOK PAGE 41 LINE 32

15.195 00103.00.00

Sunray Mid-Continent Oil Company  
Tulsa, Oklahoma

Tulsa, Oklahoma  
June 2, 1959

CONTRACTOR: Stickle Drilling Company  
Drilling Commenced: May 18, 1959  
Drilling Completed: May 29, 1959

Ward R. Philip #1 C SE/4  
SE/4 SW/4 Sec. 18-15S-21W,  
Trego County, Kansas.

DRILLERS LOG

Depth Figures Indicate Base of Formation:

Surface	0
Shale & Shells	850
Sand With Shale Streaks	975
Shale & Shells	1080
Sand	1300
Shale & Red Bed	1419
Red Bed & Shale & Shells	1600
Anhydrite	1655
Shale & Shells	2360
Shale & Lime	2510
Lime & Shale	2650
Lime	2735
Lime & Shale	3210
Shale & Lime	3485
Lime & Shale	3560
Shale & Lime	3665
Lime & Shale	3789
Lime	3975
Lime & Shale	4040
Cherty Lime & Shale	4072
Lime Chert & Shale	4102
Shale & Lime	4130
Lime, Shale & Sand	4175
Conglomerate	4220
Conglomerate & Miss., Lime & Chert	4272 TD

I, Fred E. Stickle hereby certify the above to be a true and complete Drillers Log of Sunray Mid-Continent Oil Company's Ward R. Philip #1 C SE/4 SE/4 SW/4 Section 18-15S-21W, Trego County, Kansas.

Fred E. Stickle  
Fred E. Stickle

Lillian T. Bonham  
Notary Public

February 13, 1960  
My Commission Expires

PLUGGING  
FILE SEC 18 T 15 R 21W  
BOOK PAGE 41 LINE 32