


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas



Locate well correctly on above
Section Plat

Trego County, Sec. 16 Twp. 14 Rge. 21 (E) W (W)
Location as "NE/CNW&SW" or footage from lines NW NE SE
Lease Owner Raymond Oil Company
Lease Name Kroeger Well No. 1
Office Address Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 4/8/68 19
Plugging completed 4/17/68 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Nichols
Producing formation Depth to top Bottom Total Depth of Well 4010 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8-5/8 | 243' | none |
| | | | | 5 1/2 | 4008' | 3225' |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked bottom, ran sand to 3900' and dumped 5 sacks of cement.
Loaded hole, shot pipe at 3391', 3298', 3207', worked pipe at
no gain intension. Pumped 40 barrels water, 48 barrels oil, chased
plug to 3200' and worked pipe loose, pulled 104 joints. Pumped
5 sacks hulls, 35 sacks gel mud and 130 sacks of cement. Tallied pipe.

PLUGGING COMPLETE.


RECEIVED
STATE CORPORATION COMMISSION
NOV 4 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN to before me this 31st day of October, 1968



My commission expires February 15, 1971
Margaret Melcher Notary Public.

ROCI #1 KROEGER
 NW NE SE Sec. 16-14S-21W
 Trego County, Kansas

ELEVATION: 2212 KB
 2208 DF
 2206 GL

| | | |
|----------------------|-------------------|--------------------------|
| Drilling Contractor: | Company Tools | Casing Record |
| Date Commenced: | October 31, 1967 | 8-7/8" @ 243' w/185 sx |
| Date Completed: | November 10, 1967 | 5-1/2" @ 4008' w/125 sx. |

Figures Indicate Bottom of Formation

| <u>Formation</u> | <u>Depth</u> |
|----------------------|--------------|
| Shale | 245 |
| Shale & Shells | 1015 |
| Sand | 1275 |
| Shale & Shells | 1667 |
| Red Bed & Shale | 1722 |
| Shale | 2134 |
| Shale & Lime Streaks | 2180 |
| Shale & Lime | 2555 |
| Lime & Shale | 3380 |
| Lime | 3519 |
| Lime & Shale | 3525 |
| Lime | 3674 |
| Lime w/Shale | 3716 |
| Lime & Chert | 3768 |
| Lime | 3907 |
| Cherty Lime | 3935 |
| Lime & Chert | 3944 |
| Shale & Chert | 3975 |
| Sand | 3980 |
| Lime | 3995 |
| Shale & Sand | 4010 |
| RTD | 4010 |

RECEIVED
 STATE CORPORATION COMMISSION
 APR 1 1968
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS:
 COUNTY OF SEDGWICK)

I hereby certify that the above and foregoing is true and correct to the best of my knowledge.

Wm M Raymond
 Wm. M. Raymond

SUBSCRIBED and sworn to before me, this 29th day of November, 1967.

Ronnie Donnelly
 Ronnie Donnelly - Notary Public

My commission expires:
February 15, 1971

