

15.195.00134.00.00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Trego

County. Sec. 5 Twp. 14S Rge. 21 (E)XX (W)

Location as "NE/CNWSW" or footage from lines SW SW NE

Lease Owner Welch & Olsson Drilling Co. Inc.

Lease Name 203 Rule Bldg. FLAX Well No. 1

Office Address Wichita, Ks.

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 8-17 19 56

Application for plugging filed 8-17 19 56

Application for plugging approved 8-17 19 56


Plugging commenced 8-17 19 56

Plugging completed 8-17 19 56

Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production None 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326, Hays, Kansas.

Producing formation Depth to top Bottom Total Depth of Well 4065 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	190.55'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded to 185'. Put in half sack of hulls. Set plug and cemented with 20 sacks of cement. Mudded to 35'. Put in half sack of hulls. Set plug and cemented with 10 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 25 1956  
8-25-1956  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Welch & Olsson Drilling Co. Inc.  
Address 203 Rule Bldg. Wichita, Ks.

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
R.E. Welch (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) [Signature]  
203 Rule Bldg. Wichita, Ks.  
(Address)

SUBSCRIBED AND SWORN to before me this 24 day of August, 19 56

My commission expires June 12, 1959 Edith Erker Notary Public.

PLUGGING  
FILE SEC. 5 T. 14 R. 21W  
BOOK PAGE 92 LINE 29

WELL LOG.

WELCH & OLSSON DRILLING COMPANY, INC.

ELEVATION: 2246 R.B.

CONTRACTOR: WELCH & OLSSON DRILLING CO. INC.

COMMENCED DRLG: 8-4-56

FLAX #1  
SW SW NE of Sec. 5-14S-21W, Trego County, Kansas.

Compl. Drlg: 8-17-56

Production: D & A.

Casing Record.

Set 190.55' of 8 5/8" with 175 sacks of cement.

(Figures indicate bottom of formations.)

<u>FORMATIONS:</u>	<u>DEPTHS.</u>	<u>FORMATION TOPS.</u>
Shale:	900	Anhydrite (Drlr. top) 1616 (plus 630)
Sand:	1250	Heebner: 3564 (-1318)
Shale & Red Bed:	1400	Lansing-Kansas City 3602 (-1356)
Red Bed & Shale:	1600	Base Kansas City: 3851 (-1605)
Shale & Shells:	1616	Marmaton: 3864 (-1618)
Anhydrite:	1655	Marmaton Chert: 3926 (-1700)
Shale & Shells:	2245	Conglomerate: 3998 (-1752)
Shale & Lime:	2360	Arbuckle: 4033 (-1787)
Shale & Shells:	2500	
Shale W/lime Strks:	2575	
Shale & Lime:	2614	
Lime & Shale:	2780	
Shale W/Lime Strks:	2910	
Lime & Shale:	3025	
Shale & Lime:	3380	
Lime & Shale:	3540	
Lime:	3947	
Cherty Lime:	3975	
Lime:	4010	
Conglomerate:	4040	
Lime:	4065	

STATE OF KANSAS )  
                          ) SS:  
SEDGWICK COUNTY, )

**RECEIVED**  
STATE CORPORATION COMMISSION  
AUG 25 1956  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above is a true and correct copy of Drillers Log of well drilled in the approximate center of the SW SW NE of Section 5, Township 14 South, Range 21 West, Trego County, Kansas.

WELCH & OLSSON DRILLING COMPANY, INC.  
BY [Signature]  
R. E. WELCH

Subscribed and sworn to before me this 24th day of August, 1956.

[Signature]  
Edith Erker, Notary Public.

My commission expires:  
June 12, 1959

**PLUGGING**  
FILE SEC. 5 T. 14 R. 21W  
BOOK PAGE 92 LINE 29