


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Trigo County. Sec. 25 Twp. 13 Rge. 21 (E)W (W)
Location as "NE/CNW/SW" or footage from lines SW/SW/NW
Lease Owner I.O. Miller
Lease Name Phillip Well No. #1
Office Address 619 Brown Building Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed 10-25-1965
Application for plugging filed 10-25-1965
Application for plugging approved 10-25-1965
Plugging commenced 10-25-1965
Plugging completed 10-25-1965
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation 0 Depth to top 0 Bottom 0 Total Depth of Well 4003 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
SURFACE PIPE				8-5/8"	209'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with rotary mud to a depth of 540' where 1st plug was set using 20 sacks cement. Filling hole with rotary mud to a depth of 200' where 2nd plug was set using 20 sac cement. Rotary mud was used to fill hole to a depth of 40' where 3rd plug was set using 10 sac cement and filling hole to surface.

RECEIVED
STATE CORPORATION COMMISSION

NOV 19 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. J. Dreiling & Sons, Inc.
Address Route # 2 Victoria, Kansas

STATE OF Kansas, COUNTY OF Ellis, ss.
I, Leo F. Dreiling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling
Leo F. Dreiling Route # 2 Victoria, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of October, 1965

Elmer Weltz
Notary Public.

My commission expires October 26, 1965

L. J. DREILING and SONS, Inc.

VICTORIA, KANSAS

15.195.30107.00.00

WELL LOG

Company I. O. Miller

Sec. 25 Twp. 13 Rng. 21

Farm Phillip

No. # 1

Location SW / SW / NW

Total Depth 4003'

County Trego

Comm. 10-16-65

Comp. 10-25-65

Elevation: D. F. 2295'

K. E. 2298'

G. R. 2293'

Contractor L. J. Dreiling & Sons, Inc.
Victoria, Kansas
Casing Record

Cement Record

Production:

209' 8-5/8"

150 sacks

D & A

Figures Indicate Bottom of Formations

0'	40'	Surface Soil & Post Rock
40'	70'	Sand & Gravel
70'	209'	Shale
209'	1120'	Shale
1120'	1250'	Sand
1250'	1358'	Sand
1358'	1647'	Red Bed & Shale
1647'	1691'	Anhy.
1691'	1705'	Shale & Shells
1705'	2081'	Shale & Shells
2081'	2195'	Shale & Shells
2195'	2420'	Shale & Lime
2420'	2630'	Shale & Lime
2630'	2837'	Shale & Lime
2837'	3040'	Shale & Lime
3040'	3282'	Shale & Lime
3282'	3448'	Shale & Lime
3448'	3544'	Lime & Shale
3544'	3605'	Lime
3605'	3650'	Lime
3650'	3725'	Lime
3725'	3785'	Lime
3785'	3850'	Lime
3850'	3923'	Lime
3923'	3953'	Lime & Chert.
3953'	3955'	Lime
3955'	3981'	Lime & Chert.
3981'	3992'	Lime
3992'	3997'	Lime
3997'	4001'	Lime
4001'	4003'	Lime
4003'	T.D.	

RECEIVED
STATE CORPORATION COMMISSION

NOV 19 1965

CONSERVATION DIVISION
VICTORIA, KANSAS

STATE OF KANSAS)
)ss
COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc. upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Phillip # 1.

Leo F. Dreiling
LEO F. DREILING

Emm J. Wolf
NOTARY PUBLIC

Subscribed and sworn to before me this 27th, October 1965.