

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
11 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Trego County, Sec. 15 Twp. 13S Rge. (E) 21W (W)

Location as "NE/CNW/SW" or footage from lines C NE SE
Lease Owner Chester Williams & D & D Drilling Co., Inc.
Lease Name Muhlheim Well No. 11
Office Address 419 First National Building
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 7-9-62 19
Application for plugging filed 7-12-62 19
Application for plugging approved 7-9-62 19
Plugging commenced 7-9-62 19
Plugging completed 7-9-62 19
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3960 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface	o	o	242'	8 5/8"	6-30-62	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 600' 1st plug set with 20 sacks
cement, Filled with heavy mud to 240' inside surface casing set
2 nd plugg with 20 sacks of cement, filled with heavy mud to
35' set 3rd plug with 8 sacks of cement, 2 sacks of cement in
rat hole.

RECEIVED
STATE CORPORATION COMMISSION
JUL 19 1962
CONSERVATION DIVISION
Wichita, Kansas

7-19-1962

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor D & D Drilling Company, Inc.
Address 308 Schweiter Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
James I. Daniels (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James I. Daniels
James I. Daniels
308 Schweiter Bldg. Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of July, 19 62
Colleen Chapple
Colleen Chapple Notary Public.

My commission expires 11-18-62

ROTARY DRILLED LOG

OPERATOR: Chester Williams & D & D Drilling Company
 CONTRACTOR: D & D Drilling Company, Inc.
 Well: Muhlheim #1
 G NS 53 Sec. 15-13-21W
 Trago County, Kansas

Comm: 6-30-62
 Comp: 7-9-62

FORMATION:

Sand & Gravel	242'
Gravel & Sand	85'
Shale	1080'
Sand	1305'
Shale & Red Bed	1110'
Shale	7135'
Shale & Lime	2510'
Shale	2323'
Shale & Lime	3025'
Lime & Shale	2140'
Lime	3960'
Rotary Total Depth	3060' D & D

REMARKS:

Set 3 joints of 8 5/8" surface pipe at 242' cemented with 175 sacks of 11-5.

RECEIVED
 STATE CORPORATION COMMISSION

JUL 19 1962

CONSERVATION DIVISION
 Wichita, Kansas

AFFIDAVIT

STATE OF KANSAS

COUNTY OF SEDGWICK

VS

James I. Daniels of lawful age, being duly and solemnly sworn on oath says: I am a resident of Wichita, Sedgwick County, Kansas, and I hereby know and on oath saith, that, the above drilling log covering the Muhlheim #1 located in the G NS 53 Section 15-13-21W, Trago County, Kansas, is true and correct to the best of my knowledge and belief, further affiant saith not.

D & D Drilling Company, Inc.

James I. Daniels

James I. Daniels

Subscribed and sworn to before me this 11th day of July, 1962.

Collen Chapple
 Collen Chapple - Notary Public

My Commission expires November 10, 1962.